BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division-1,

Tender Notification No:BBMP/EE/DD/Ten/05/2010-11 ITEM No-08

SCHDULE-B

NAME OF WORK: Construction of BS Slab Drain & Culverts at Medarahalli, in Ward No-12, In Shettyhalli Sub-Division.

Sl. No.	Description	Unit	Approximate Qty	Rates Quoted by Contractor		Amount
				Figures	words	
1	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specifications.	Cum	197.56	121.82	Rupees One Hundred Twenty One and Eighty Two Paise Only	24067.55
2	Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete 7.5 cms thick	Cum	482.40	286.29	Rupees Two Hundred Eighty Six and Twenty Eight Paise Only	138104.56
3	Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	8.28	3148.14	Rupees Three Thousand One Hundred Forty Eight and Thirteen Paise Only	26066.56
4	Providing and laying in position plain cement concrete of mix 1:2:4 using 20mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	25.92	4124.76	Rupees Four Thousand One Hundred Twenty Four and Seventy Five Paise Only	106913.72
5	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1:5:3) for raft foundation, column footing, main and secondary beams.	Cum	12.10	4222.22	Rupees Four Thousand Two Hundred Twenty Two and Twenty One Paise Only	51071.93
6	providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Q	14.26	4892.25	Rupees Four Thousand Eight Hundred Ninety Two and Twenty Four Paise Only	69743.90

7	Providing and removing centering, shuttering, strutting, propping etc., for edges o slabs and breaks in f r, cills, plinth including cost of all materials, labo... complete as per specification.	Cum	86.40	471.05	Rupees Four Hundred Seventy One and Five Paise Only	40698.96
8	Conveying the excavaed earth to a distance of 2kms with all lead & lifts including loading & unloading charges etc., complete.	Cum	194.45	68.34	Rupees Sixty Eight and Thirty Four Paise Only	13289.35
	TOTAL			-	-	469956.53
	Percentage Quoted by Contractor					(-)6.00%

I am prepared to take up the work at rate mentioned in schedule 'B'

Executive Engineer,
Dasarahalli Division-1,
B.B.M.P. Bangalore